

COST ^{VS} VALUE 2019

www.costvsvalue.com

remodeling
YOUR TOOLBOX FOR SUCCESS

Project Descriptions

BATHROOM ADDITION—MIDRANGE

Add 6x8-foot bathroom over crawlspace with poured concrete walls. Use cultured-stone vanity top with molded sink; standard chrome faucets; 30x60-inch white fiberglass tub/shower with ceramic tile surround; single-lever temperature and pressure-balanced faucet; white low-profile toilet; general and spot lighting; electrical wiring to code; mirrored medicine cabinet; linen storage closet or cabinet; painted trim; ceramic tile floor.

BATHROOM ADDITION—UPSCALE

Add new 100-square-foot master bath to existing master bedroom over crawlspace. Include 42x42-inch neo-angle shower with ceramic tile walls, accent strip, recessed shower caddy, body-spray fixtures, and frameless glass enclosure. Put in freestanding soaker tub with high-end faucets; stone countertop with two sinks; two mirrored medicine cabinets with lighting; a compartmentalized commode area with one-piece toilet; and a humidistat-controlled exhaust fan. Use larger matching ceramic tiles on the floor, laid on diagonal with ceramic tile base molding. Add general and spot lighting and waterproof shower fixture. Cabinetry has custom drawer base, wall cabinets. Extend HVAC. Electric in-floor heating.

BATH REMODEL—MIDRANGE

Update existing 5x7-foot bathroom. Replace all fixtures to include 30x60-inch porcelain-on-steel tub with 4x4-inch ceramic tile surround; new single-lever temperature and pressure-balanced shower control; standard white toilet; solid-surface vanity counter with integral sink; recessed medicine cabinet with light; ceramic tile floor; vinyl wallpaper.

BATH REMODEL—UPSCALE

Expand existing 35-square-foot bathroom to 100 sf within existing house footprint. Relocate all fixtures. Include 42x42-inch neo-angle shower with ceramic tile walls with accent strip, recessed shower caddy, body-spray fixtures, and frameless glass enclosure. Include freestanding soaker tub with high-end faucets; stone countertop with two sinks; two mirrored medicine cabinets with lighting; a compartmentalized commode area with one-piece toilet; and a humidistat-controlled exhaust fan. Use all color fixtures. Use larger matching ceramic tiles on the floor, laid on diagonal with ceramic tile base molding. Add general and spot lighting including waterproof shower fixture. Cabinetry has custom drawer base, wall cabinets. Extend HVAC. Electric in-floor heating.

UNIVERSAL DESIGN BATH REMODEL

Update existing 5x7-foot space to be wheelchair-accessible (zero-threshold, 36-inch-wide door) and install flat-panel electrical switches at sitting level (36 to 42 inches above floor). Replace toilet with comfort height fixture featuring elongated bowl and bidet-type seat. Remove existing bathtub and install curbless, tiled, walk-in shower with adjustable showerhead, fold-out seat, thermostatic

mixing valve, and bi-directional glass door. Replace flooring with electric radiant heat beneath new luxury vinyl tile flooring. Install adaptive living vanity with easy-grasp handles and adjustable mirror. Install LED lights, infrared ceiling light, night light, and ultra-quiet vent fan with humidity-sensing controls. Install ceramic tiles on walls with two contrasting color stripes. Install nine towel bars that can support 250 pounds and reconfigure storage to be accessible from a seated position.

MINOR KITCHEN REMODEL—MIDRANGE

In functional but dated 200-square-foot kitchen with 30 linear feet of cabinetry and countertops, leave cabinet boxes in place but replace fronts with new shaker-style wood panels and drawer fronts, including new hardware. Replace cooktop/oven range and slide-in refrigerator with new energy-efficient models. Replace laminate countertops; install midpriced sink and faucet. Add new resilient flooring. Finish with painted walls, trim, and ceiling.

MAJOR KITCHEN REMODEL—MIDRANGE

Update outmoded 200-square-foot kitchen with functional layout of 30 linear feet of semi-custom wood cabinets, including 3x5-foot island; laminate countertops; and standard double-tub stainless-steel sink with standard single-lever faucet. Include energy-efficient range, vented range hood, built-in microwave, dishwasher, garbage disposal, and custom lighting. Add new resilient flooring. Finish with painted walls, trim, and ceiling.

MAJOR KITCHEN REMODEL—UPSCALE

Update outmoded 200-square-foot kitchen with 30 linear feet of top-of-the-line custom white cabinets with built-in sliding shelves and other interior accessories. Include stone countertops with imported ceramic- or glass-tile backsplash; built-in refrigerator, commercial-grade cooktop and vent hood, wall oven, and built-in microwave unit. Install high-end undermount sink with designer faucets and water filtration system. Add new general and task lighting, including low-voltage undercabinet lights. Install tile or similar flooring that looks like wood.

MASTER SUITE ADDITION—MIDRANGE

Add 24x16-foot master bedroom suite over crawlspace. Include walk-in closet/dressing area, freestanding soaker tub, separate 3x4-foot ceramic tile shower, and double-bowl vanity with solid-surface countertop. Carpet the bedroom floor; put tile in bath. Paint walls, ceiling, and trim. Install general and spot lighting, exhaust fan.

MASTER SUITE ADDITION—UPSCALE

Add 32x20-foot master bedroom suite over crawlspace. Add spacious sleeping area with lounging/sitting area adjacent to large master bath. Include custom bookcases and built-in storage with millwork details; high-end gas fireplace with stone hearth and custom mantle; and walk-in closet/dressing area with natural light, mirrors, and linen storage. Add French doors. Bathroom includes walk-in shower with

COST VS VALUE 2019

dual-shower system, stone walls and floor, and custom frameless glass enclosure. Add freestanding soaker tub. Include two sinks in separate custom vanities with stone countertops and large mirrors. Create partitioned area for luxury one-piece toilet. Outside the bath, add 5-foot-long hospitality center with bar sink, undercounter refrigerator, custom cabinetry, stone countertop, and microwave. Include soundproofing, in-floor heating, custom wall finishes and hardware, general and spot lighting, and high-end lighting controls.

DECK ADDITION—COMPOSITE

Add 16x20-foot deck using pressure-treated joists supported by 4x4-inch posts anchored to concrete piers. Install composite deck material in a simple linear pattern. Include built-in bench and planter of the same decking material. Include stairs, assuming three steps to grade. Provide a complete railing using a matching system made of the same composite as the decking material.

DECK ADDITION—WOOD

Add 16x20-foot deck using pressure-treated joists supported by 4x4-inch posts anchored to concrete piers. Install pressure-treated deck boards in a simple linear pattern. Include built-in bench and planter of the same decking material. Include stairs, assuming three steps to grade. Provide a complete railing system using pressure-treated wood posts, railings, and balusters.

BACKYARD PATIO

Install 20x20-foot flagstone patio on flat ground behind home. Connect house and patio via a lift-and-slide glass door. Put gas-powered fire pit in the center of the patio and surround it with four mid-priced, all-weather deck chairs. Opposite home, install stone-veneer modular kitchen unit with gas grill, mini-refrigerator, sink, and storage. On each corner, erect 20x20-foot cedar pergola capable of holding an awning that can shade the flagstone area. Install mid-priced, low-voltage lights on pergola sufficient to illuminate patio at night. Install underground gas and electrical connections.

ENTRY DOOR REPLACEMENT—STEEL

Remove existing 3-0/6-8 entry door and jambs and replace with new 20-gauge steel unit, including a clear, dual-pane half-glass panel, jambs, and aluminum threshold with composite stop. Door is factory finished with same color both sides. Exterior brick-mold and 2.5-inch interior colonial or ranch casings in poplar or equal prefinished to match door color. Replace existing lockset.

GRAND ENTRANCE—FIBERGLASS

Remove existing 3-0/6-8 entry door and cut and reframe opening for a 12-36-12 entrance door with dual sidelights. Move double-gang electrical box with two switches. Fiberglass door blank matches upscale entry, including color, threshold, lockset, and decorative half-glass; sidelights match door. PVC-wrapped exterior trim in color to match existing trim; wider interior colonial or ranch casings (3.5-inch to cover new jack studs) in hardwood stained to match door. All work to be completed in one day.

GARAGE DOOR REPLACEMENT

Remove and dispose of existing 16x7-foot garage door and tracks. Install new four-section garage door on new heavy-duty galvanized steel tracks; reuse existing motorized opener. New door has a lifetime warranty, and is made with high-tensile-strength steel with two coats of factory-applied paint, is foam insulated to minimum R-12, and includes thermal seals between pinch-resistant panels. Windows in top panel are ½-inch insulated glass. Hardware includes galvanized steel hinges and ball-bearing urethane rollers.

SIDING REPLACEMENT

Replace 1,250 square feet of existing siding with new siding installed to manufacturer's specifications. Include factory trim at all openings and corners.

MANUFACTURED STONE VENEER

Remove 300-square-foot continuous band of existing vinyl siding from bottom third of street-facing façade. Replace with adhered manufactured stone veneer, including 36 linear feet (LF) of sills, 40 LF of corners, and one address block. Installation includes two separate layers of water-resistive barrier laid over bare sheathing, corrosion-resistant lath and fasteners, and nominal ½-inch-thick mortar scratch coat and setting bed. Outline entry archway; use an 8x10-inch keystone and a soldier course of flats on either side.

WINDOW REPLACEMENT—VINYL

Replace 10 existing 3x5-foot double-hung windows with insulated, low-E, simulated-divided-light vinyl windows with a custom-color exterior finish. Trim exterior to match existing; do not disturb existing interior trim.

WINDOW REPLACEMENT—WOOD

Replace 10 existing 3x5-foot double-hung windows with insulated, low-E, simulated-divided-light wood windows. Interior finish of stained hardwood; exterior finish of custom-color aluminum cladding. Trim exterior to match existing; do not disturb existing interior trim.

ROOFING REPLACEMENT—ASPHALT SHINGLES

Remove and dispose of existing roofing to bare wood sheathing. Install 30 squares of min. 235-lb. fiberglass asphalt shingles (min. 25-year warranty) with new 30-lb. felt (or equivalent synthetic) underlayment, galvanized drip edge, and mill-finish aluminum flashing. Assume a rectangular hip roof; custom flashing at two average-size skylights; and custom cap treatment at vented ridge.

ROOFING REPLACEMENT—METAL

Remove and dispose of existing roofing to bare wood sheathing. Install ice-barrier membrane at roof perimeter, and premium-grade synthetic underlayment over roof. Install 3,000 square feet of prefinished, standing-seam metal roofing with matching pre-formed accessories, including drip edge, gable trim, and vented ridge flashing. Assume a rectangular hip roof; custom flashing at two average-size skylights; custom cap treatment at vented ridge.

PROJECT TYPE	SALT LAKE CITY			MOUNTAIN			2019 NATIONAL AVERAGES		
	Job Cost	Resale Value	Cost Recouped	Job Cost	Resale Value	Cost Recouped	Job Cost	Resale Value	Cost Recouped
Bathroom Addition Midrange	\$ 44,133	\$ 23,408	53.0%	\$ 44,841	\$ 25,390	56.6%	\$ 47,427	\$ 28,726	60.6%
Bathroom Addition Upscale	82,090	48,625	59.2%	84,023	45,920	54.7%	87,704	51,000	58.1%
Bath Remodel Midrange	19,053	10,875	57.1%	19,377	11,985	61.9%	20,420	13,717	67.2%
Bath Remodel Upscale	61,034	30,875	50.6%	62,013	33,356	53.8%	64,743	38,952	60.2%
Bath Remodel Universal Design	31,757	13,909	43.8%	32,087	17,811	55.5%	33,374	20,868	62.5%
Minor Kitchen Remodel Midrange	21,442	20,933	97.6%	21,726	17,439	80.3%	22,507	18,123	80.5%
Major Kitchen Remodel Midrange	63,231	49,600	78.4%	64,113	38,841	60.6%	66,196	41,133	62.1%
Major Kitchen Remodel Upscale	125,925	87,500	69.5%	127,648	76,212	59.7%	131,510	78,524	59.7%
Master Suite Addition Midrange	122,149	82,800	67.8%	124,612	71,443	57.3%	130,986	77,785	59.4%
Master Suite Addition Upscale	254,093	138,700	54.6%	259,438	125,764	48.5%	271,470	136,820	50.4%
Deck Addition Composite	18,184	13,864	76.2%	18,443	12,271	66.5%	19,150	13,232	69.1%
Deck Addition Wood	13,612	10,955	80.5%	13,294	9,881	74.3%	13,333	10,083	75.6%
Backyard Patio	54,162	32,545	60.1%	54,774	30,319	55.4%	56,906	31,430	55.2%
Entry Door Replacement Steel	1,746	1,015	58.1%	1,769	1,136	64.2%	1,826	1,368	74.9%
Grand Entrance Fiberglass	8,689	6,500	74.8%	8,808	6,257	71.0%	8,994	6,469	71.9%
Garage Door Replacement	3,513	3,250	92.5%	3,550	3,502	98.6%	3,611	3,520	97.5%
Window Replacement Vinyl	16,132	12,850	79.7%	16,340	11,644	71.3%	16,802	12,332	73.4%
Window Replacement Wood	19,807	14,400	72.7%	20,026	13,422	67.0%	20,526	14,530	70.8%
Siding Replacement	14,831	12,600	85.0%	15,317	11,545	75.4%	16,036	12,119	75.6%
Manufactured Stone Veneer	8,448	10,980	130.0%	8,731	8,422	96.5%	8,907	8,449	94.9%
Roofing Replacement Asphalt Shingles	21,453	15,000	69.9%	21,614	14,171	65.6%	22,636	15,427	68.2%
Roofing Replacement Metal	36,651	22,000	60.0%	36,577	21,965	60.1%	38,600	23,526	60.9%

CONFIDENCE LEVEL: 95% +/-4.4

CONFIDENCE LEVEL: 95% +/-1.4